



**STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION  
DEC 26 1973  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company  
 Complete Address 217 N. Water, Wichita, Kansas 67202  
 Lease Name <sup>RNE</sup> R. E. P. DeVine "A" (SWD) Well No. 3  
 Location SE SE SE Sec. 14 Twp. 11 Rge. (E) (W) 19  
 County Ellis Total Depth 3486'  
 Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well SWD D & A  
 Other well as hereafter indicated Oil Well converted to SWD  
 Plugging Contractor Co. Tools  
 Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 1:30 P Day 22 Month 12 Year 1973

The above well was plugged as follows:

Total Depth 3486' 8 5/8 esg set at 1273' cwe 475 sk.  
5 1/2 esg set at 3482' ew 100 sk cem.  
On 9-29-64 2651' of 5 1/2 esg was cutoff and recovered.  
8 5/8 esg PBTD at 1255' & dumped 1 1/2 sk calseal cem. W/dump bailer.  
Perf. 8 5/8 esg from 740'-995'.  
Pumped down 8 5/8 esg with 25 sk gel & water W/400 lbs hulls & 100 sk cem W/100  
lbs hulls. Max PP 500# SIP 250#.

I hereby certify that the above well was plugged as herein stated.

Signed: Les F. Messing  
Well Plugging Supervisor

RECORDED  
DATE 12/28/73  
ENV. NO. 8329-W