

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION 22 SE SE NE

SEC. 12 TWP. 11 RGE. 19

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Gassoway

Operator Graham Messman Rinehart Address Wichita, Kans

Field _____ County Ellis

Total Depth 3398 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 197' circulated with cement - 5 1/8" at 3390'
with 100 sax behind - Baker plugs to 3460' - top perf
3434'.

Filled with chat to 3360', set 5 sax cement with dump bailer.
shot pipe at 2945', pumped in 30 sax Aquagel, pulled pipe,
Pumped 8 5/8" cementing plug to 225', followed by 75 sax
cement, filling hole from 225' to 0' with cement.

Cementing by Sun Cementing Co

STATE OF KANSAS

MAY 25 1951

CONSERVATION DIVISION
Wichita, Kansas
[Signature]
District Conservation Agent

Date 5-23-51

PLUGGING
WELLS SEC. 12 T. 11 R. 19
BOOK PAGE 24 LINE 33