

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW SW NW

SEC. 12 TWP. 11 RGE. 19

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Gassoway Bldg. & Loan Bldgs

Operator V. D. Sidey Address Russell, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3646 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 93' circulated with cement - 5 1/2" at 3642.

Lead wool, mud, rock, calseal and 6 sax cement to 3288'.

pulled 3185' 5 1/2", filled hole with mud to 233', set rock

bridge and 15 sax cement, mud to 35', set rock and 10 sax

cement to bottom cellar.

**PLUGGING**  
FILE SEC 12 TWP 11 RGE 19  
PAGE 14 LINE 5  
2-1-52

[Signature]  
District Conservation Agent  
Date 1-30-52