

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051 - 21,667-0000 (of this well)

Operator's Full Name J. B. Collins

Complete Address 1007 Cody, Suite "A", Hays, Ks.

Lease Name Gladys Well No. 4

Location 165°S SW SE NE Sec. 12 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3455'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dreiling Oil

Address Victoria, Ks. License No.

Operation Completed: Hour 10:30 A Day 31 Month 3 Year 1979

The above well was plugged as follows:

RTD 3455' 8 5/8 csg set 167' cwc 135 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 160' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
APR - 2 1979
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4-4-79
INV. NO. 9351-W

Signed: [Signature]
Well Plugging Supervisor