

CP-3

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECORDED BY
INDEXED BY
STATE CORPORATION COMMISSION
AUG 7 1962
CONSERVATION DIVISION
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co
 Complete Address: 820 Union Natl Bldg Wichita, Kans
 Lease Name Albert Well No. 6
 Location NW NW SW Sec. 10 Twp. 11 Rge. (E) (W) 19
 County Ellis Total Depth 3607
 Abandoned Oil Well x Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractors: Southwest Casing Pulling & Globe Cementing
 Address: Great Bend, Kans License No. 399
 Operation Completed: Hour 2PM Day 2 Month 8 Year 62

The Above well was plugged as follows:

~~8 5/8' 200' circulated with cement - 5 1/2" 3509' with 150 sax cement & squeezed with cement at 817'.~~

Sand back to 3505', set 3 sax cement with dump bailer - pulled 570' 5 1/2" to 500', ~~circulated hole with heavy gel mud through 5 1/2" at 500' (20 sax Gel)~~ displaced 20 sax cement through 5 1/2" at 500', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 190', heavy mud to 35', cement to bottom cellar- 10 sax .

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 8/6/62
INV. NO. 5489-W

Signed: Edon Petty
Well Plugging Supervisor