

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

10-22-62 OCT 22 1962
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 820 Union Natl Bk Bldg Wichita, Kansas

Lease Name Falconberry Well No. 4

Location CW $\frac{1}{2}$ W $\frac{1}{2}$ NW Sec. 10 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3627

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kansas License No. 399

Operation Completed: Hour 5PM Day 15 Month 10 Year 62

The Above well was plugged as follows:

8 5/8" 157' circulated with cement - 4 $\frac{1}{2}$ " 3620' with 200 sax cement.

PB 3594' - Perf 3279' - sand back to 3250', set 4 sax cement with dump

bailer - pulled 2005' 4 $\frac{1}{2}$ " to 500', circulated hole with heavy gel mud

through 4 $\frac{1}{2}$ " at 500', displaced 20 sax cement through 4 $\frac{1}{2}$ " at 500', mud to

180' - displaced 20 sax cement through 4 $\frac{1}{2}$ " at 180', mud to 35', set plug

and 10 sax cement to bottom cellar.

Mudding and cementing by Southwest Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/19/62
INV. NO. 5874-W

Signed: [Signature]
Well Plugging Supervisor