

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SU NE NW

SEC. 10 TWP. 11 RGE. 19W

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Falkenberg *Falkenberg 27 1/2 Sec. North of Well*

Operator Okmar Oil Co Address Wichita, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3523 Feet.

Plugging Contractor R & S Pipe Pulling

Plugging Contractor's License No. 1

Address \_\_\_\_\_  
(Describe briefly the manner in which the well was plugged)

8 5/8" at 220' circulated with cement - 5 1/2" at 3518' with  
150 sax cement behind.

Filled with sand to 3500', set 4 sax cement with dump bailer,  
pulled 2450' 5 1/8" - filled hole with mud to 220', set rock and  
15 sax cement, mud to 35', set rock and 10 sax cement to bottom  
cellar.

District Conservation Agent

Date 6-23-55

**PLUGGING**  
SEC 10 T 11 R 19 W  
PAGE 30 LINE 39

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1955  
CONSERVATION DIVISION  
WICHITA, KANSAS