

*Y*

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 8 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name KWB Oil Property Management, Incorporated,  
Complete Address Box #65, Great Bend, Kansas.  
Lease Name Delzeit Well No. 1  
Location SE-SE Sec. 13 Twp. 11 Rge. (E) (W) 32  
County Logan Total Depth 4720  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Leben Drilling, Incorporated,  
Address Box #186, Great Bend, Kansas. License No.         
Operation Completed: Hour 11:30 AM Day 4 Month 12 Year 1969

The above well was plugged as follows:

287'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1350'.

Circulated hole with heavy mud. Pulled DP to 1575' and displaced 100 Sx. cement thru  
DP from 1575' to 1250'. Pulled DP to 300' and displaced 25 Sx. cement thru DP from  
300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dinkel*  
Well Plugging Supervisor

1000-W  
12/9/69