

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company.

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Delzeit Well No. A-1

Location CNW-SE Sec. 13 Twp. 11 Rge. (E) (W) 32

County Logan Total Depth 1686'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 1:45 PM Day 12 Month 1 Year 1973

The above well was plugged as follows:

251'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1400'.

Circulated hole with heavy mud. Pulled DP to 1625' and displaced 110 Cu. Ft. cement
thru DP from 1625' to 1300'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Daniels
Well Plugging Supervisor

1/15/73
INV. NO. 6853-W