

R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -051 -21,466-0000 (of this well)

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 1978
WICHITA, KANSAS

Operator's Full Name Crude Producers, Inc.

Complete Address P. O. Box 55, Russell, Kansas

Lease Name Armbrister "B" Well No. 1

Location SE NE SW Sec. 6 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3745'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor John Farmer

Address Russell, Kansas License No.

Operation Completed: Hour 11 A Day 7 Month 5 Year 1978

The above well was plugged as follows:

RTD 3745' 8 5/8 csg set 225' cwc 160 sk. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.
Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey
Well Plugging Supervisor

DATE 5-8-78
INV. NO. 7259-W