

2

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 18-39 County: Ellis

Location: SW SW NW Sec. 0 Twp. 11 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3718

I have this date completed supervision of plugging of:

Lease Name: Keller Well No. 1

Operator's Full Name: Ross Welch

Complete Address: 1509 Briggs Ave Wichita, Kans

Plugging Contractor: Wigging & Lamb

Address: Mc Pherson, Kans License No. 358

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 11 AM Day 10 Month 3 Year 59

The above well was plugged as follows:

8 5/8" at 137' circulated with cement - 5 1/2" 3097' with 120 sax cement behind.

Lane Wells plugs to 3504', perforated 3425'.

Filled with sand to 3410', set 4 sax cement with dump bail let, pulled

800' 5 1/2" to 600', circulated hole with heavy mud, displaced 20 sax cement

through 5 1/2" at 600', heavy mud to 180', displaced 20 sax cement through

5 1/2" at 180', heavy mud to 55', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC 6 T. 11 R. 19
BOOK PAGE 18 LINE 39

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1959
CONSERVATION DIVISION
Wichita, Kansas