

4-071181

7-7

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,629-0000
130' N. & 160' W. of
NW NE SE /4 SEC. 24, 11 S, 32 W
2440 feet from S section line
1150 feet from E section line

Operator license# 5135

Lease Durham Well # 1

Operator: John O. Farmer, Inc.

County: Logan

Address: P.O. Box 352
Russell, Kansas 67665
Martin K. Dubois

Well total depth 4660 ^{151.45} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing - Abercrombie Drilling License# -

Address: Oakley, Kansas 67748 - Great Bend, Kansas 67530

Company to plug at: Hour: 3:30 P.M. Day: 7 Month: July Year: 1996

Plugging proposal received from: Tony Martin

Company: Abercrombie Drilling Phone: 913-483-3144

Were: 8 5/8" - 208' S.P. cwc w/160 sxs. 60/40 pozmix - 2% gel - 3% c.c. - 1/4# Flocele.
By Allied Cement. Elev. 3007' - Anhy. 2509' - Miss. Well - Mud conditions 50 vis - 9.2 wt. -
11.5 W.L. - chlorides at 4014' - 1000 ppm. Order 190 sxs 60/40 pozmix - 6% gel - 1/4# flocel
per sack. Pump in with pump truck - spot and displace all cement through drill pipe - heavy
mud between all plugs. 25 sxs at 2520' - 100 sxs at 1590' - 40 sxs at 250' - 10 sxs at 40' -
15 sxs in rathole.

Plugging Proposal Received by: Marion Schmidt

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 3:30 P.M., Day: 7, Month: July, Year: 1996

Actual plugging report: Abercrombie Drilling ordered 190 sxs 60/40 pozmix - 6% gel - 1/4# flocele per sack. Pumped in with pump truck. Circulated hole. Heavy mud between all plugs.
1st. plug at 2520' w/25 sxs. cement.
2nd. plug at 1590' w/100 sxs cement.
3rd. plug at 250' w/40 sxs cement.
4th. plug at 40' w/10 sxs cement.
15 sxs in rathole (circulated)

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1996

Remarks: Cemented by Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 3007 GL

I did[] / did not[] observe the plugging.

Marion Schmidt
(agent)
Form CP-2/3

INVOICED

NO.

DATE 7-23-96

AV. NO. 46053