

3-27 4-032227

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,276-0000
68'W. of C.
S2 NE NW /4 SEC. 11, 11, 32 W
4290 feet from S section line
3368 feet from E section line

Operator license# 5131

Lease: Jones Well # 2

Operator: Thunderbird Drilling, Inc.

County: Logan 151.45

Address: P.O. Box 97
Ellinwood, Kansas 67526

Well total depth 4660 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 288 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67526

Company to plug at: Hour: A.M. Day: 27 Month: March Year: 1997

Plugging proposal received from: James Ray

Company: Mike's Testing & Salvage Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Order sand and common cement.
Allied Cement Company.

Vertical stamp: RECEIVED
MAY 12 1997
PLUGGING DIVISION

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [], Part [], None []

Completed: Hour: 10:45 A.M., Day: 27 Month: March, Year: 1997

Actual plugging report: 8 5/8" set at 288' w/200 sxs.cwc. 4 1/2" set at 4659' w/170 sxs.
Prod Perfs 4086' - 4588'. Sanded back to 3990' w/4 sxs common cement on sand with bailer.
Shots at 2493' - 2005' - 1800' - 1700'. Recovered 1700' of 4 1/2". Mixed and pumped 100 sxs
cement blend with 350# hulls mixed into 2500'. Pulled 4 1/2" to 300'. Pumped 65 sxs cement
blend with 150# hulls to circulate to surface. Pulled rest of casing. Hole remained full.
Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Any plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE MAY 13 1997
INV. NO. 48096