

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20005-00-00  
Spot: CNWSW Sec/Twnshp/Rge: 11-11S-32W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: OAKLEY UNIT (SCHMITT 1 Well Number: 2-1  
County: LOGAN Total Vertical Depth: 4680 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size feet: \$ 152.10  
Surface Casing: Size 8.625 feet: 238 175 SX CMT  
Production: Size 5.5 feet: 4675 225 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/11/2002 9:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-6781

Proposed Plugging Method: Ordered 350 sxs of Mid-con II cement and 1000# hulls.  
Plug thru tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/11/2002 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" Surface casing set at 238' w/175 sxs cement.  
5 1/2" Production casing set at 4675' w/225 sxs cement.  
D.V. Tool at 2286' - circulated cement to surface with 430 sxs cement.  
Ran tubing to 3000' - pumped 50 sxs cement with 300# hulls.  
Pulled tubing to 2000' - pumped 50 sxs cement with 400# hulls.  
Pulled tubing to 1000' - pumped 80 sxs cement with 200# hulls.  
Cement circulated to surface.  
Pulled tubing to surface.  
Connected to 5 1/2" casing and pumped 35 sxs cement.  
S.I.P. 200#.  
Connected to 8 5/8" surface casing.  
Pumped 1 bbl water. S.I.P. 200#.  
Plug complete.

RECEIVED  
DEC 18 2002  
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS SCHMITT #1. SWIFT CEMENT COMPANY.

Plugged through: TBC

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

INVOICED

DATE 12-19-02

WV. NO. 2003060953

Form CP-2/3

DEC 11 2002

MURFIN DRILLING CO., 11-11-32W  
 NADEL & GUSSMAN & RAYMOND OIL #1 SCHMITT C. NW SW  
 WICHITA, KANSAS:  
 CONTR CO. TOOLS CTY LOGAN

GEOL \_\_\_\_\_ FIELD OAKLEY CONF

E 3046 R8 CM 6/9/70 <sup>CARD</sup> ISSUED 9/3/70 IP P 243 BO + 32% WTR  
 LANS 4110-4237  
 GR 44

API 15-109-20,005

| LOG TOPS   | DEPTH | DATUM |                                                                                                                |
|------------|-------|-------|----------------------------------------------------------------------------------------------------------------|
| U BLAINE   | 2177  | + 869 | 8 5/8" 288/175sx; 5 1/2" 4675/225sx                                                                            |
| L BLAINE   | 2288  | + 758 | DST(1) 4056-4093(LANS)/30-30-30-30, 3' OIL, 125' OSM, BHP 1281-1281#, FP 33-91#                                |
| ANHY       | 2538  | + 506 | DST(2) 4102-10(LANS)/30-30-90-30, 600' GAS, 1540' FL (1500' OIL & 40' MO), BHP 1262-1198#, OIL 37°, FP 54-539# |
| B ANHY     | 2565  | + 481 |                                                                                                                |
| FR         | 3006  | + 40  |                                                                                                                |
| NEVA       | 3408  | - 362 | DST(3) 4111-17(LANS)/30-30-30-30, 30' OSPM, BHP 1226-1198#, FP 31-45#                                          |
| TOP        | 3824  | - 778 |                                                                                                                |
| HFFB       | 3988  | - 942 | DST(4) 4170-17(LANS)/30-30-90-30, GTS/30", 3230' CGO, BHP 1244-1244#, FP 273-1162#                             |
| TOR        | 4013  | - 967 |                                                                                                                |
| LKC        | 4030  | - 984 | DST(5) 4121-55(LANS)/30-30-90-30, 500' MSW, BHP 1335-1290#, FP 29-329#                                         |
| R LKC      | 4309  | -1263 |                                                                                                                |
| MARM       | 4337  | -1291 | DST(6) 4211-27(LANS)/30-30-90-30, GTS/65", 2009' OIL, 40°, BHP 1334-1282#, FP 64-695#                          |
| CHER       | 4534  | -1488 |                                                                                                                |
| MISS(ST.L) | 4622  | -1576 | DST(7) 4228-50(LANS)/30-30-90-30, 120' OCM, 120' MO, BHP 439-402#, FP 36-119#                                  |
| LTD        | 4676  | -1630 |                                                                                                                |
| RTD        | 4680  | -1634 | DST(8) 4252-82(LANS)/30-30-30-30, 30' OSPM, BHP 100-92#, FP 36-54# (OVER)                                      |

INDEPENDENT OIL & GAS SERVICE

MURFIN DRILLING CO., 11-11-32W  
 NADEL & GUSSMAN & RAYMOND OIL #1 SCHMITT C. NW SW

- DST(9) 4286-4310/30-30-30-30, 10' OSPM/FREE OIL, BHP 36-36#, FP 29-29#  
 DST(10) 4313-53(MARM)/30-30-90-30, GTS/1'30", 1585' OIL, 40°, BHP 1317-1244#, FP 73-567#  
 DST(11) 4474-4507(MARM)/30-30-90-30, GTS/1'50", 640' OIL, 240' OCM, 240' W, BHP 1189-1189#, FP 45-420#  
 DST(12) 4532-60(CHER)/30-30-30-30, 5' M, BHP 31-31#, FP 45-420#  
 DST(13) 4574-4600(CHER)/30-30-90-30, 1200' GAS, 280' OIL, 31°, 60' OCM, BHP 457-448#, FP 36-128#

MICT, PF 20/4487-97(MARM) 1500 ACID SWB DN TO 900' OB & SWB 28BF 70% OIL/1ST HR 25BF 2ND HR/TR WTR, PF 12/4342-48(MARM) SET BP @ 4375 250 ACID SWB LD & SWB 48 BO/2HRS N/W, PF 3/4215, 3/4222, 3/4237 SET PLUG @ 4255 500 ACID SWB LD & SWB 154BO N/W/3HRS 2400' OB, SET PLUG @ 4204, PF 9/4186-89 2000 ACID SWB LD & SWB AVG 758OPH/4HRS, PF 4065, 4069, 4085, 4105, 4110 SET PLUG @ 4150 500 ACID SWB LD & SWB 80BO/2HRS CO PLUGS & SET BP @ 4300 TO PRODUCE LANS-KC, POP

NOTE: TOTAL ESTIMATED SWAB TESTS 2258OPH FROM MARM & LANS-KC

P EST 96 BO PLUS WTR PER DAY