

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20287-00-00  
Spot: N2NENENW Sec/Twnshp/Rge: 11-11S-32W  
5080 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: OAKLEY UNIT Well Number: 1  
County: LOGAN Total Vertical Depth: 4700 feet

Operator License No.: 8996

Conductor Pipe: Size feet:

Operator Name: MID-CONTINENT RESOURCES, IN

Surface Casing: Size 8.625 feet: 280

Address: PO BOX 399  
GARDEN CITY, KS 67846

Production: Size 4.5 feet: 4700

Liner: Size feet:

152.75

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/28/2000 9:00 AM

Plug Co. License No.: 8996

Plug Co. Name: MID-CONTINENT RESOURCES, INC.

Proposal Rcvd. from: DALE CHRISLER

Company: MID-CONTINENT RESOURCES, IN Phone: (316) 275-7461

Proposed  
Plugging  
Method:

Ordered 300 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 11/28/2000 10:00 AM

KCC Agent: CARL GOODROW

Actual Plugging Report:

This was a tight hole, little information available.

8 5/8" set at 280' cwc.

4 1/2" set at 4700' cement n/a.

Prod. Perf LKC n/a.

Two stage was done - information n/a.

Plugging:

4 1/2" squeezed with 245 sxs cement blend with 800# hulls mixed in to Max. P.S.I. 1000#. S.I.P. 500#.

8 5/8" annulus squeezed with 10 sxs cement blend to Max. P.S.I. 500#. Held.

Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 6 2000

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed Carl Goodrow PART II

(TECHNICIAN)

INVOICED

DATE: 12/7/00

NO. 2001061072

Form CP-2/3

NOV 30 2000

replacement card

ENERGY EXPLORATION  
WICHITA KS

11-11S-32W  
200'FNL & 2310'FWL, SEC

# 1 OAKLEY UNIT

site: 1/8 S OF OAKLEY KS  
contr: ABERCROMBIE DRILLING

ty: LOGAN  
field: OAKLEY

API 15-109-20287

geol:  
fr date 06/13/83 spd date 07/06/83 drig comp 07/16/83 card issued 10/20/83 last revised 01/19/98

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

ELV: 3048 KB, 3043 GL  
tops.....depth/datum  
RTD.....4700 -1652  
NO TOPS RPTD

IP status:  
OIL, P 120 BOPD, LKC, INTV NA, 09/01/83  
INFO RELEASED: 1/19/98 - WAS TIGHT HOLE  
CSG: 8 5/8" 280+, 4-1/2" 4700  
COMMENT: REDESCRIBED LOC - IS ALSO 200'FNL &  
330'FEL, NW/4  
NO CORES OR DSTS RPTD  
MICT - CO, PF (LKC) INTV NA, AC'D, SO, POP, IPP 120  
BOPD, 9/1/83, UPDATE: PROD HISTORY P 99,845 BO  
TOTAL FROM 8/83 - 7/97; P 166 BO (7/97) - NO OTHER  
INFO RELEASED BY OPERATOR OR ON KCC  
RECORDS: ALL REQUESTS FOR INFO DENIED

COPYRIGHT 1998  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS