

2-23

155

R

6 070750

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 109-20,470-0000

N/2 SW NW, SEC. 10, T 11 S, R 32 W/E

3630 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

Lease Name Nickelson Well # H #1

Operator: Energy Exploration Inc.

County Logan 154.38

Name & Address 1002 S. Broadway

Well Total Depth 4750 feet

Wichita, Ks. 67211

Conductor Pipe: Size 0 feet

Kevin Howard

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling IDC. License Number Tag #180

Address 801 Union Center Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 23 Month: Feb Year: 19 89

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling Inc. (phone)

were: 8 5/8" 305' S.P. cwc w/190 sks common 2% Gel 3% Cal Cl. B. J. Titan.

Miss. Well Elev. 3067. Anhy 2581' No cir problems, mud condition, 49 vis.

9.3 weight. 10 water loss. Proposal 215 sks 60/40 Poz 6% Gel 3% Cal Cl. 30 sks at

2610'. 100 sks w/1 sk F.C. at 1660'. 50 sks at 350'. 10 sks at 40'. 15 sks in

rathole 10 sks mouse hole. Circulate.

Plugging Proposal Received *[Signature]* Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30PM Day: 23 Month: Feb Year: 19 89

ACTUAL PLUGGING REPORT Ordered 215 sks 60/40 Poz 6% Gel 3% Cal Cl. Spot with

drill stem. Recondition hole. Heavy mud between plugs. 1st plug at 2610'

w/30 sks cement. 2nd plug 100 sks w/1 sk F.C. at 1660'. 3rd plug at 350' w/50 sks

cement. 4th plug 10 sks at 40'. 15 sks rathole (Cir) 10 sks mousehole (cir)

Cemented by B. J. Titan. RECEIVED STATE CORPORATION COMMISSION

MAR 07 1989

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
Should observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

DATE 3-7-89

Signed *[Signature]* Marion J. Schmidt (TECHNICIAN)

INV. NO. 24078
2-23