

15.6.
R

4-060851

3-5

TO;
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,212-0000
68' W. of
SE NW /4 SEC. 11, 11 S, 32 W
3300 feet from S section line
3368 feet from E section line

Operator license# 5131 Lease: Jones Well # 1

Operator: Thunderbird Drilling, Inc. County: Logan

Address: P.O. Box 97
Ellinwood, Kansas 67526
Well total depth 4675 ^{151.93} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 293 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 2:00 P.M. Day: 5 Month: March Year: 1996

Plugging proposal received from: Rich McEntire

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 250 sxs 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

RECEIVED
KANSAS
APR 11 1996

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:00 P.M., Day: 5, Month: March, Year: 1996

Actual plugging report: 8 5/8" to 293 with 180 sxs. 4 1/2" to 4674' with 175 sxs. Perfs
from 4112' - 4575'. Sanded to 4060' and spotted 4 sxs cement with dump bailer. Shot casing
at 2500' - 1800' - 1700' with no loose casing. Shot at 1622' and recovered casing. At 1600'
mixed and pumped 85 sxs cement with 300# hulls. Pulled casing to 1000' and pumped 40 sxs
cement with 200# hulls. Pulled casing to 320' and circulated cement with 80 sxs cement.
Pulled casing with cement in cellar.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 3025 GL

INVOICED
did not [X] observe the plugging.

DATE APR 11 1996
INV. NO. 45195

Herb Deines
(agent)
Form CP-2/3