

6030486

API NUMBER 15-109-20,283-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NWSE NW SEC. 10, T 11 S, R 32

TECHNICIAN'S PLUGGING REPORT

3630 feet from S section line

3630 feet from E section line

Operator License # 5318

Lease Name H.E. NICKELSON Well # 1

Operator: ENERGY RESERVES GROUP INC. County LOGAN 153.24

Name & Address 925 PATTON ROAD

Well Total Depth 4715 feet

GREAT BEND, KANSAS

Conductor Pipe: Size _____ feet

67530

Surface Casing: Size 8 5/8 feet 291'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE, KANSAS

Company to plug at: Hour: AM Day: 17 Month: 6 Year: 19 85

Plugging proposal received from RONNIE

(company name) KELSO CASING (phone) _____

were: 8 5/8 SET @ 291' w/100 SX. 5 1/2 SET @ 4712' w/150' OV. @ 2578 w/4706X.

Order sand com. Cmt., shoot off strip pipe. Order 180 SX. 50/50 POZ

6 1/2 GEL. 3 1/2 SEC 40 SX. GEL. 4 SX. HULLS 8 5/8 W.P. B.J. TITAN Cmt. Co. WELBROCK

WATER TRUCK. PBTD 4694 TOPPER. 4214

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 AM Day: 17 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT Dump SAND ON PBTD @ 4694 TO 4150' SPOT w/ BAILER 5 SX. COM

CMT. ON SAND. RECOVERED 1240' CASING - Pump DOWN 8 5/8 - 3 SX. HULLS + 12 SX. GEL.

100 SX. CMT. MIX. + 1 SX. HULLS - 28 SX. GEL. RELEASE 8 5/8 W.P. - 80 SX. CMT. MIX.

MAX. PSE 300* CLOSE IN 150* Plug COMPLETE

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____

(if additional description is necessary, use BACK of this form.)

INVOICED

(if applicable) observe this plugging.

DATE 6-26-85

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 8726

38
6-21-85
mjs