

6 090354

12-9-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-21,357-0000
NW , SEC. 6, T 11 S, R 19 W/E
3020 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5015

Lease Name Keller Well # 3
County Ellis 120.41
Well Total Depth 3705 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 236

Operator: Hellar Drilling Co. Inc.
Name & Address 711 Petroleum Bldg.
Wichita, Kansas 67202

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number
Address Russell, Kansas

Company to plug at: Hour: 2:00PM Day: 9 Month: December Year: 19 87

Plugging proposal received from Carl Gilpin

(company name) Hellar Drilling Co. Inc. (phone) 316-267-2845

were: 8 5/8" set at 236' w/200 sks. 4 1/2" set at 3705' w/150 sks. 4 1/2" squeezed at
858' w/200 sks (1-9-78). 4 1/2" shot at 1205' - 1213' w/10 shots on July 16,
1987 (Great Guns) Perfs 3155' - 63'; 3420' - 25'; 3437' - 42'; 3466' - 69';
3537' - 41'. Order 300 sks 65/35 Pozmix 10% Gel and 2% Lite w/10 sks Hulls
and 1 sk Flocele.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:00PM Day: 9 Month: December Year: 19 87

ACTUAL PLUGGING REPORT Pumped down 4 1/2" casing w/25 sks cement w/1lb. Flocele per sk.
followed by 225 sks cement mixed w/8 sks Hulls, maximum pressure, 600 Psi. Shut in 400 Psi.
Pumped down 8 5/8" and 4 1/2" annulus w/50 sks cement w/2 sks Hulls. Maximum Psi 400.
Shut in 150 Psi.

Remarks: Elevation 2128' Anhydrite 1515' Arbuckle 3694'

(If additional description is necessary, use BACK of this form.)
observe this plugging.

INVOICED
DATE 12-15-87
INV. NO. 19285

Signed Edwin A. Schumacher
(TECHNICIAN)
Edwin A. Schumacher

RECEIVED
TIFC 15 1987
CONSERVATION DIVISION
Wichita, Kansas
D