

State of Kansas



FORM CP-2

15-051-22663-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Inc. has this
date requested permission to plug the following described well:

Operator's Full Name: Beren & Company

Complete Address: 506 Rule Bldg., Wichita, Kansas 67202

Lease Name: Mai Well No. #1

Location: Center of NW of NW Sec. 7 Twp. 11 Rge. 19 (E) (W)

County: Ellis Total Depth: 3740'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereafter indicated: _____

Mr. Bill Draper was instructed to plug the well as follows:

8 5/8"-207' s.p. cuc. w/165 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

5 sacks of cement in rat hole, and 5 sacks of cement in mouse hole.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

[Signature] NOV 2 1981
Conservation Division Agent
Wichita, Kansas