



15:109-20004-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dan Cook of KWB Oil Property Management, has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: KWB Oil Property Management, Incorporated

Complete Address: Box #65, Great Bend, Kansas

Lease Name: Delzeit Well No. 1

Location: SE-SE Sec. 13 Twp. 11 Rge. (E)(W) 32

County: Logan Total Depth 4720' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

287'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1350'.

Circulate hole with heavy mud. Pull DP to 1575' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. D. Nichols
Conservation Division Agent