



15-109-20007-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: Murfin, Nadel & Gussman and Raymond,

Complete Address: 617 Union Center Building, Wichita, Kansas,

Lease Name: Schmitt Well No. 2

Location: 150 West of CNE-SW Sec. 11 Twp. 11 Rge. (E)(W) 32

County: Logan Total Depth 4650' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Niernberger was instructed to plug the well as follows:

256'--8 5/8" Surface casing, cement circulated with 175 Sx. Bottom joint of surface casing had come loose, gone down hole 103' and were unable to get below 353' with DP and circulating spear.

Lay down DP, and squeeze well with 135 Sx. cement staged with drilling mud so as to have 100 Sx. cement from 1975' to 1650', 25 Sx. cement from 275' to 200' and 10 Sx. cement from 40' to bottom of cellar.

Very truly yours,

W. L. Nichol  
Conservation Division Agent