

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-165-21,642-0000

LEASE NAME Dietz

WELL NUMBER 1

330 Ft. from S Section Line

2,310 Ft. from E Section Line

SEC. 21 TWP. 16 RGE. 16 (X) or (W)

COUNTY Rush

Date Well Completed 10-22-93

Plugging Commenced 10-22-93

Plugging Completed 10-23-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Carmen Schmitt

ADDRESS PO Box 47, Great Bend, KS. 67530

PHONE#(316) 793-5100 OPERATORS LICENSE NO. 6569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-22-93 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,535'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	1,067'	Cmtd. w/375 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Spot 50 sax cement @1,095' thru drill pipe. Spot 40 sax cement @450' thru drill pipe. Push wiper plug to 40', dump 10 sax cement and 1 sax hulls on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas (Employee of Operator) or (Operator) Contractor of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 1st day of November, 19 93

Ruth Phillips  
Notary Public

My Commission Expires: \_\_\_\_\_



RECEIVED  
STATE CORPORATION COMMISSION  
NOV 03 1993

CONSERVATION DIVISION  
WICHITA, KANSAS




15-16S-21642-0000  
*Shields*

*Russell, Kansas*

WELL LOG

Operator: Carmen Schmitt  
Well: Dietz #1  
Commenced: October 15, 1993  
Completed: October 23, 1993  
Contractor: Shields Drilling Co.

Well Description: SW SW SE  
Sec. 21-16S-16W  
Rush Co., Kansas



CASING RECORD		
Size	Run	Pulled
8 5/8"	1,067'	Cmtd. w/375 sax

Elevation: 1,955' KB  
Treatment:  
Production: D & A  
Tops:

..... Figures Indicate Bottom of Formations .....

Shale & rock	435'	
Shale & sand	977'	
Shale	1,057'	
Anhydrite	1,092'	
Shale	1,750'	
Shale & lime	3,260'	
Lime	3,535'	RTD

Notes

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 03 1993  
CONSERVATION DIVISION  
Wichita, Kansas