

TYPE OR PRINT  
 NOTICE: Fill out completely and return  
 to Cons. Div. office within 30 days.

LEASE OPERATOR Rains & Williamson Oil Co., Inc.

SPOT LOCATION Cent - NE - NE - SW

ADDRESS P. O. BOX 1645

SEC. 22 TWP. 16 S. RGE 16 (E) or (W)

CITY, STATE, ZIP great bend, Kansas 67530

COUNTY RUSH

PHONE# (620) 793-6656 OPERATORS LICENSE NO. 5146

Date Well Completed 2-22-1974

Character of Well Oil Well  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 3-7-2001

Date Plugging Completed 3-9-2001

Date plugging proposal was approved on 1-10-2001 (date)

Richard Lacey (KCC District Agent's Name)

ACO-1 filed? Yes If not, is well log attached?

Producing Formation(s) Depth to Top Bottom T.D. 3550

Show depth and thickness of all water, oil and gas formations.

L, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
				8 5/8"	1041'	NONE
				5 1/2"	3546'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Well Perfs @ 3302-06, 3364-67, 3461-64. Bottom Plug - pump 25 sx. cement & 200# hulls - displaced to 3050' - Perforated @ 1000' - Pumped 225 sx. cement down 5 1/2" casing - Circulating cement up 8 5/8" x 5 1/2" annulus to surface. (Used 60/40 Pozmix w/ 6% Gel)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co.

License No. 99996

Address P.O.Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rains & Williamson Oil Co., Inc.

CITY OF Kansas COUNTY OF Sedgwick, ss.

Claude Blakesley (Employee of Operator or (Operator) of above-described well, being first)

Notary on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature) Claude Blakesley  
 Address) P.O.Box 1645, Great Bend, Kansas 67530

RECEIVED  
 KANSAS CORPORATION COMMISSION

MAY 7 2001

SUBSCRIBED AND SWORN TO before me this 4th day of May, 2001

Patricia A. Thome  
 Notary Public

My Commission Expires: 6-18-2001



CONSERVATION DIVISION  
 Form CP-4  
 Revised 12-

OR