

API NUMBER 15-165-21,645-0000

LEASE NAME Kaiser "A"

WELL NUMBER 2

4290' Ft. from S Section Line

3300' Ft. from E Section Line

SEC. 28 TWP. 16 RGE. 16 (#/or (W))

COUNTY Rush

Date Well Completed 2-11-94

Plugging Commenced 11-17-94

Plugging Completed 11-17-94

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458 Hays, Kansas 67601-0458

PHONE# (913) 625-6374 OPERATORS LICENSE NO. 03456

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-9-94 (date)

by Mr. Lacy (KCC District Agent's Name).

Is ACO-1 filled? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation L-KC Depth to Top 3219 Bottom 3295 T.O. 3580

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	Oil & Water	3219'	3295'	8 5/8"	1075	None
				4 1/2"	3563	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Hooked to 4 1/2" - Mixed 200# of hulls ahead of 155 sx. 60/40 Poz., 8% gel. (100# Hulls in first of cement), Pump Press - 1000#. SIP - 500#. Hooked to 8 5/8". - Mixed 100# of hulls. Followed with 200 sx. 60/40 Poz., 8% gel. (100# hulls in first cement). Pump press - 800#. SIP - 500#

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Russell, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Terry W. Piesker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 458 Hays, Ks, 67601-0458

SUBSCRIBED AND SWORN TO before me this 18th day of Nov., 19 94

Linda K Pfannenstiel  
 Notary Public

My Commission Expires: 2/5/96  
 USE ONLY ONE SIDE OF EACH FORM

