


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Rush County. Sec 32 Twp. 16S Rge. 16 (E) W (W)  
Location as "NE/CNWxSWx" or footage from lines NW NW NE  
Lease Owner Frontier Oil Company  
Lease Name Allen "B" Well No. 1  
Office Address 1720 Wichita Plaza - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed February 18 19 66  
Application for plugging filed April 3 19 68  
Application for plugging approved April 4 19 68  
Plugging commenced April 8 19 68  
Plugging completed April 8 19 68  
Reason for abandonment of well or producing formation Non-commercial

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols  
Producing formation Topeka Depth to top 3006 Bottom \_\_\_\_\_ Total Depth of Well 3590 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	212'	8 5/8"	212'	-0-
		0	3589'	4 1/2"	3589'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mixed 10 sacks of cement followed with 30 sacks of gell mud and 90 sacks cement 6% added gel. Max. pressure 800#, minimum pressure 300#.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Company, Inc.  
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Harold R. Martin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold R. Martin  
1720 Wichita Plaza - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of April, 19 68.

Betty M. Maloney  
Notary Public.

15-165-3018-0000

DRILLERS LOG

Allen "B" No. 1

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 212'	CONTRACTOR:	Red Tiger Drilling Company	NW NW NE
w/140 sx cement	COMMENCED:	February 9, 1966	32-16S-16W
4 1/2" @ 3589'	COMPLETED:	February 18, 1966	Rush Co., Ks.
w/275 sx cement			ELEVATION: 1998 DF
			2001 RB
TOTAL DEPTH:		3590'	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Post Rock	0	70	
Shale	70	530	
Sand	530	730	
Red Bed & Shale	730	1092	
Anhydrite	1092	1130	
Shale & Shells	1130	1740	
Shale & Lime	1740	3070	
Lime	3070	3530	
Lime & Cherty Conglomerate	3530	3582	
Lime	3582	3590	

RECEIVED  
STATE CORPORATION COMMISSION  
APR 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Maxine V. Starr  
Maxine V. Starr

Subscribed and sworn to before me this 24th day of February, 1966.

Jean Holloway  
Notary Public

My Commission Expires:

5-22-66