

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-1165-00330-0000

API NUMBER 6-22-64

LEASE NAME Allen

WELL NUMBER #1

SPOT LOCATION NE-NE-Se

SEC. 32 TWP. 16 RGE. 16 (E) or (W)

COUNTY Rush

Date Well Completed 6-22-64

Plugging Commenced 12-14-90

Plugging Completed 12-14-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605, Russell, KS 67665

PHONE # (913) 483-6213 OPERATORS LICENSE NO. 3456

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Topeka Depth to top 2997 bottom 3002 T.D. 3076'

CI Plug at 2850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Topeka	Gas & Water	2997	3002	8 5/8"	200'	None
				4 1/2"	3111'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from    feet to    feet each set. -Attached-


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_  
Address Russell, Kansas

STATE OF Kansas COUNTY OF Russell, ss.

Terry W. Piesker (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker  
(Address) P.O. Box 605 Russell, Kan.



SUBSCRIBED AND SWORN TO before me this 18<sup>th</sup> day of December, 1990

Pamela K. Steckel  
Notary Public

My Commission expires: 11-19-90

15-165-00330-0000

Allen #1

- 12-13-90 Moved in and rigged up. Ran tubing in to 2806'.
- 12-14-90 Pumped 90 sx. 65/35 Poz, 6% gel. Pulled tubing up to 1800'. Spotted 75 sx 65/35 Poz, 6% gel. Pull tubing up to 831'. Mixed approximately 20 sxs. and cement circulated. Pulled tubing out of hole. Tied on to 5 1/2" casing and pressured to 1000#. SI - 500#. Got about 10 sxs. in it. Hooked to 8 5/8" casing. 30 sx. 65/35. Pressured to 1000#. SI-500#.