

LEASE NAME Legleiter #1

WELL NUMBER # 1

660 Ft. from S Section Line

2670 Ft. from E Section Line

SEC. 1 TWP. 16 RGE. 18 (R) or (W)

COUNTY Rush

Date Well Completed n/a

Plugging Commenced 8/17/94 12:30 p.m.

Plugging Completed 8/17/94 1:30

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR American Warrior Inc.

ADDRESS Box 399; Garden City, Ks. 67846

PHONE# (316) 275-9231 OPERATORS LICENSE NO. 4058

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/12/94 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Topeka Kansas City Depth to Top 3350' Bottom 3465' T.D. 3575'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	1140	8 5/8	1148	none
	Longstring	0	3575	4 1/2	3575	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from    feet to    feet each set. Sand back bottom to 3300'. Dump 4 sks. cement on top sand. Mix 8 sks. gel with 300# hulls. Mix 50 sks. Halliburton light cement, mix 12 sks. gel. with 100# hulls. Mix 100 sks. Halliburton light. Maximum pressure 1200#. Closed in 750#. Job run down 8 5/8" casing. 8/19/94 Cement down 4'. Ticket # 621864  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. \_\_\_\_\_

Address Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior Inc.

STATE OF KANSAS COUNTY OF Ellis, ss. \_\_\_\_\_

Dean Dues (Employee of Operator) or ACO Operator for above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean Dues


(Address) 1209 Haney Hays, Ks

SUBSCRIBED AND SWORN TO before me this 25th day of August, 1994

Charlotte Weder

Notary Public

My Commission Expires: 12-28-95



RECEIVED  
STATE CORPORATION COMMISSION  
AUG 26 1994