

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-21650 0000

LEASE NAME Grabbe

WELL NUMBER 1

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 3 TWP. 16 SRGE. 18 (E) or (W)

COUNTY Rush

Date Well Completed 3/5/94

Plugging Commenced 8/16/97

Plugging Completed 8/16/97

11-7-97

RECEIVED
KANSAS CORP COM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Libco, Inc.

ADDRESS P. O. Box 27119, Lakewood, CO 80227-0119

PHONE# (303) 980-4672 OPERATORS LICENSE NO. 31741

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 27, 1997 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? no

Producing Formation Penn Sand Depth to Top 3512 Bottom 3514 T.D. 3640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	dry	0	1101	8-5/8	1101	0
Lansing	dry	0	3639	5-1/2	3639	2600
Penn Sand	oil					
Arbuckle	dry					
Reagan SS	dry					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Casing shot off at 2600', pulled to 1100'. Spotted 20 sxs gel and 50 sxs cement from 1100' to 965'. Pulled to 600'. Spotted 40 sxs cement from 600' to 460'. Pulled to 40'. Spotted 10 sxs cement from 40' to surface.

Name of Plugging Contractor Paramount Casing License No. 3763

Address P. O. Box 861, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Libco, Inc.

STATE OF Colorado COUNTY OF Jefferson, ss.

Rex H. Paulens, Jr. Agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Rex H. Paulens, Jr.

(Address) 3440 Youngfield #355 Wheat Ridge CO 80033

SUBSCRIBED AND SWORN TO before me this 31 day of October, 19 97

Judy Roseman
Notary Public

My Commission Expires: 7-18-98