

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,543-0000

LEASE NAME WATT "CC"

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2970' Ft. from S Section Line

3630' Ft. from E Section Line

SEC. 15 TWP. 16SRGE. 30 (X) or (W)

COUNTY LANE

LEASE OPERATOR Slawson Exploration Company, Inc.

ADDRESS 104 S. Broadway, Suite 200 Wichita, Ks. 67202

PHONE#(316) 263-3201 OPERATORS LICENSE NO. 3988

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 2-21-90

Plugging Commenced 2-21-90 4:15 A.M.

Plugging Completed 2-21-90 7:00 A.M.

The plugging proposal was approved on February 20, 1990 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? by oper. If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	349'	8 5/8"	349	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

1st plug @ 2220' W/50 sx., 2nd plug @ 1420' W/80 sx., 3rd plug @ 380' W/40 sx.,
4th plug @ 40' W/10 sx., 15 sx. in rat hole---Total 195 sx. 60/40 Pozmix, 6% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address Russell, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Slawson Exploration Company, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or (~~OPERATOR~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson
Greg Davidson


(Address) R.R. 1 Box 183 B, Great Bend, Ks.

26th day of February, 1990

Bessie M. DeWerff
Notary Public
Bessie M. DeWerff

My Commission Expires: 5-20-93

4-27-90
APR 17 1990
SUBSCRIBED AND SWORN TO before me this
Notary Public - State of Kansas
Wichita, Kansas



FORM C-1 12/88
 EFFECTIVE DATE: 2-12-90

101-21,543-0000

State of Kansas
 NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date ... February ... 12 ... 1990
 month day year

SW SE NW Sec 15 Twp 16 S, Rg 30 East West

OPERATOR: License # 3988
 Name: SLAWSON EXPLORATION COMPANY, INC.
 Address: 104 South Broadway, Suite 200
 City/State/Zip: Wichita, Kansas 67202-4165
 Contact Person: Robert B. Jenkins
 Phone: (316) 263-3201

2970' feet from South line of Section
3630' feet from East line of Section
 (Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 6039
 Name: L.D. DRILLING, INC.

County: Lane
 Lease Name: WATT, "CC" Well #: 1
 Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
 Gas ... Storage ... Pool Ext. ... Air Rotary
 OMAO ... Disposal Wildcat ... Cable
 Seismic; ... # of Holes

Is this a Prorated Field? ... yes no
 Target Formation(s): Mississippian
 Nearest lease or unit boundary: 330'
 Ground Surface Elevation: 2786' GR. (Seis). feet MSL

If OMAO: old well information as follows:
 Operator: _____
 Well Name: _____
 Comp. Date: _____ Old Total Depth _____

Domestic well within 330 feet: ... yes no
 Municipal well within one mile: ... yes no
 Depth to bottom of fresh water: 180'
 Depth to bottom of usable water: 1500' / 1350'
 Surface Pipe by Alternate: ... 1 2
 Length of Surface Pipe Planned to be set: 340'
 Length of Conductor pipe required: None
 Projected Total Depth: 4600'
 Formation at Total Depth: Mississippian
 Water Source for Drilling Operations:

Directional, Deviated or Horizontal wellbore? ... yes no
 If yes, total depth location: _____

... well farm pond ... other
 DWR Permit #: farm pond too small to permit.
 Will Cores Be Taken?: ... yes no
 If yes, proposed zone: _____

Exp. 8/7/90 *Mode la*
Will set 340' 8 88

AFFIDAVIT

200' Alt. II Req.

PUSHER Gary Davidson
 TD 4550' FORMATION MISS
 SURFACE PIPE 349' @ 2 3/4"
 ANHYDRITE 2185-2215 ELEVATION 2786
 STARTING TIME & DATE 4:15 P.M. 2-21-90
 COMPLETION TIME & DATE 7:00 P.M. 2-21-90
 1st PLUG @ 2220 FT. W/ 50 SX
 2nd PLUG @ 1420 FT. W/ 80 SX
 3rd PLUG @ 380 FT. W/ 40 SX
 4th PLUG @ 40 FT. W/ 10 SX
 RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ 15 SX
 WATER WELL PLUGGED W/ 15 SX
 CEMENT COMPANY Allied
 TECHNICIAN CM
 TYPE OF CEMENT 6040 670

5280	1620
4950	1320
4620	990
4290	660
3960	330
3630	
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

Agent: _____ 2-13-90

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - file acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.