

15101-00015-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Lane _____ County, Sec. 16 Twp. 16 Rge. 30 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner B & R Drilling, Inc.

Lease Name Hagans Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/2/52 19

Application for plugging filed 6/30/52 19

Application for plugging approved 6/30/52 19

Plugging commenced 7/1/52 19

Plugging completed 7/1/52 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4589 Feet

Show depth and thickness of all water, oil and gas formations.

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	318	None

OIL, GAS OR WATER RECORDS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Finished running pipe back in hole, lay rest of drill pipe down. Filled Hole with heavy mud to 300', first plug set at 300', cemented with 15 sacks of cement. Filled hole with mud to 40', set second plug, cemented with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Don Roberts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Roberts

Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 52

Clara Fennell
Notary Public.

My commission expires 6-17-54

24-2675-S 2-52-20M

PLUGGING
FILE SEC. 1676 R 50
BOOK PAGE 27 LINE 23

15.100.00015.0000

B & R Drilling, Inc.
Logans No. 1

NW NW NW 16-16-30
Lane County, Kansas

Total depth: 4589'
Comm. 6/9/52
Comp. 7/2/52

Casing

Cement

8 5/8" Set @ 318

175 sacks of Monarch

Formation	Depth
Sand-gravel	60
Shale	100
Sand-shale	520
Shale	940
Sandy shale	1225
Shale-shell	1340
Sand	1380
Shale-sand	1445
Red bed-shale	1575
Line-PT Iron	1600
Shale-shells-red bed	1764
Sand-red bed	1850
Shale-red bed	2025
Sand-shale	2050
Line-shale	3750
Line	4589'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Lora Betty

Subscribed and sworn to before me this 7th day of July, 1952.

Wm. Edmund

Notary Public

My commission expires: 6-17-54

PLUGGING
FILE 16-16-30
27-23

FILE
STATE COURT

CONF