

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-159-00682-

LEASE NAME Boy #1

WELL NUMBER OWWO

SPOT LOCATION NE NW NW

SEC. 21 TWP. 21s RGE. 10w (E) or (W)

COUNTY Rice

Date Well Completed \_\_\_\_\_

Plugging Commenced 7/30/85

Plugging Completed 8/12/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Lebsack Oil Production, Inc.

ADDRESS Box 489, Hays, Ks. 67601

PHONE # (913) 625-3046 OPERATORS LICENSE NO. 5210

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3448'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	204'	none
				5 1/2"	3447'	1413'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3320' & 5 sacks cement. Shot pipe at 2300', 2220', 2055', 1812', 1630', 1523', & 1413'. Pulled 46 joints of pipe. Plugged well with 5 hulls, 20 gel, released plug, & 100 sacks 60/40 poz 4% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 13<sup>th</sup> day of August, 1985

My Commission expires: \_\_\_\_\_



Irene Hoover  
Notary Public

W E L L L O G

Holl & Lebsack, Boy #1 Washdown  
NE NW NW, Section 21-21S-10W  
Rice County, Kansas

ELEVATION: 1725' GL; 1727' DF; 1730' KB.

PIPE RECORD: 8 5/8" set at 204' with 195 sacks cement.

C  
O  
P  
Y

Originally drilled to 3443' by Sholom Drilling for Icer Addis August 25, 1962. Completed September 6, 1962. (Dry & Abandoned)

CONTRACTOR: Isern Drilling Company

ROTARY COMMENCED: May 23, 1969  
ROTARY COMPLETED: May 27, 1969

PIPE RECORD: 5 1/2" set @ 3446' with 225 sacks cement.

OLD TOPS (Scout Card)

Heebner	2878
Brown Lime	3011
Lansing	3041
Base Kansas City	3278
Viola	3336
Simpson Dol	3375
Arbuckle	3432
Total Depth	3442

Drilled 5' of new hole making the present total depth 3448'.

STATE OF KANSAS )  
COUNTY OF BARTON ) ss

I, W. F. Banks, Drilling Superintendent of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

*W. F. Banks*  
\_\_\_\_\_  
W. F. Banks

Subscribed and sworn to before me on this 28th day of May, 1969.

*George A. Meyer*  
\_\_\_\_\_  
George A. Meyer, Notary Public

My commission expires February 10, 1971.