

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-101-20,543-0000

LEASE NAME Roemer

WELL NUMBER #1

       Ft. from S Section Line

       Ft. from E Section Line

SEC. 13 TWP. 16S RGE 30W XX (or (W))

COUNTY Lane

Date Well Completed       

Plugging Commenced 3/3/89

Plugging Completed 3/7/89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Ted's Consulting Service

ADDRESS 318 N. Ninnescah  
 Pratt, KS 67124

PHONE# (316) 672-7838 OPERATORS LICENSE NO. 3476

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on        (date)

by        (KCC District Agent's Name).

Is ACO-1 filed?        If not, is well log attached?       

Producing Formation        Depth to Top        Bottom        T.D. 4570'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	323	none
				4 1/2	4564	806

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Plugged bottom with sand to 4300', dumped 4 sacks cement, shot @1205',  
pumped 25 sacks 60/40 poz 6% gel, displaced to 1200', shot @1000', 806',  
pumped 5 sacks gel, 50 cement, pulled to 400', pumped 40 sacks cement,  
pulled last joint, pumped 10 sacks to circulate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ted's Consulting Service

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso 11-5-89

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 15th day of March, 19 89

James Hoover  
 Notary Public

My Commission Expires:       

