

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20597-0000

LEASE NAME D. E. Roemer

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER A 2

2230 Ft. from S Section Line

4210 Ft. from E Section Line

SEC. 13 TWP. 16 RGE. 30 ~~XXX~~ or (W)

COUNTY Lane

Date Well Completed 12/30/81

Plugging Commenced 12/09/91

Plugging Completed 12/09/91

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 125 N. Market, #1075 Wichita, KS 67202

PHONE# (316) 265-3351 OPERATORS LICENSE NO. 5151

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/4/91 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Pawnee Depth to Top 4400 Bottom 4411 T.D. 4411

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|---|---------|------|----|-------|--------|------------|
| Pawnee | Oil | 4400 | 11 | 8 5/8 | 327 | 0 |
| | | | | 4 1/2 | 4400 | 0 * |
| *Stage collar at 2218 cemented to surface with 500 sx 50/50 poz 6% gel. | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mix 25 sx poz 10% gel with 500# hulls and displace with 135 sx 65/35 poz 10% gel, 2% econolite. Finish displacement with cement to surface at 1000 PSI.

Shut in 1000 PSI and held.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gear Petroleum Co., Inc. License No. 5151

Address 125 N. Market, #1075 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gear Petroleum Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim Thatcher



(Address) 125 N. Market, #1075 Wichita, KS 67202
STATE CORPORATION COMMISSION
SUBSCRIBED AND SWORN TO before me this 20th day of December, 19 91

DEC 23 1991

Polly Tilton
Notary Public

My Commission Expires: 8/1/93

WELL LOG

15-101-20597-0000

CHIEF DRILLING CO., INC.
905 CENTURY PLAZA
WICHITA, KANSAS 67202

#2 ROEMER - A
100' SE of NE NW SW
SEC. 13-16S-30W
Lane County, Kansas

CONTRACTOR: WARRIOR DRILLING CO.
CASING RECORD: 8 5/8" @ 327' w/200 sx.

COMMENCED: December 19, 1981
COMPLETED: December 30, 1981

| FORMATION | FROM | TO | ELEVATIONS: |
|--------------|------|------|-------------|
| Surface Sand | 0 | 329 | 2811 GR. |
| Sand & Clay | 329 | 1435 | 2815 D.F. |
| Sand & Shale | 1435 | 2117 | 2818 K.B. |
| Anhydrite | 2117 | 2815 | |
| Shale | 2815 | 3389 | |
| Shale & Lime | 3389 | 3949 | |
| Shale | 3949 | 4286 | |
| Lime | 4286 | 4411 | |
| RTD | 4411 | | |


4 1/2" @ 4400' w/175 sx.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE of NE NW SW Sec. 13-16S-30W Lane County, Kansas, to the best of my knowledge and belief.

STATE OF KANSAS COMMISSION

CHIEF DRILLING CO., INC.



NOV 8 1991

F. W. Shelton, Jr.
F. W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 5th day of January, 1982.