

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-071-20,007-0000

LEASE NAME Spears

WELL NUMBER #1

SPOT LOCATION 3300' FSL & 1980 ^{FEL}

SEC. 14 TWP. 20 RGE. 40 (E) or (W)

COUNTY Greeley

Date Well Completed 11-71?

Plugging Commenced 8-29-88

Plugging Completed 8-31-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hughes Seewald

ADDRESS Box 2587, Liberal, Ks. 67905

PHONE # (316) 624-3767 OPERATORS LICENSE NO. 9922

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Winfield Depth to top 2820 bottom 2839 T.D. 2840'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	415'	0'
Production				4 1/2"	2840'	1540'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 20 sks. cement to 2620' Pressured to 500 lbs.

Pump 40 sks. cement @ 1540' - mud 1440' to 450'

Pump 40 sks. cement 450 to 350'

Put bridge and 10 sks. cement 40' to 3'

Cut off 3 5/8", 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (~~Employer~~) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 31 day of August, 1988

Sondra L. Eves
Notary Public

My Commission expires: 12-6-88



SEP - 3 1988
9-8-88
STATE CORPORATION COMMISSION
Wichita, Kansas