

LEASE NAME Wallace

WELL NUMBER ONE (1)

SPOT LOCATION C SW NE

SEC. TWP. RGE. (E) or (W)

COUNTY Greeley

Date Well Completed

Plugging Commenced 6-5-90

Plugging Completed 6-8-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hughes Seewald

ADDRESS Box 2587, Liberal, Ks. 67905-2587

PHONE # (316) 624-3767 OPERATORS LICENSE NO. 9922

Character of Well gas
(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached?

Producing formation winfield Depth to top 2802 bottom 2825' T.D. 2833'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	400'	0'
Production				4 1/2"	2833'	1380

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls & 20 sks. cement to 2450'
Pressured to 750 lbs. Pump 80 sks. cement 1300' to 1000'
Mud 1000' to 650' - Pump 50 sks. cement 650' to 500'
Mud 500' to 430' - Pump 40 sks. cement 430' to 300'
Mud 300' to 40' - Bridge 840 sks. 40' to 3', cut off 8 5/8" & cap.
Mr. Dan Godrow witnessed for KCC

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor MIDWEST CASING PULLING SERVICE License No. 6497
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (employee of operator) or
(~~operator~~) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

6-12-90



SUBSCRIBED AND SWORN TO before me this 11th day of June, 19 90

Sondra L. Eves
Notary Public

My Commission expires: 12-6-92