

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-071-20,485-0000

LEASE NAME Foster

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

3960 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 24 TWP. 20 RGE. 40 (E) or (W)

LEASE OPERATOR Bartling Oil Co.

ADDRESS 8550 Katy Freeway, Suite 128, Houston, TX

COUNTY Greeley

PHONE# (713) 465-1093 OPERATORS LICENSE NO. 7271
⁷⁷⁰²⁴

Date Well Completed 2-3-90

Character of Well Gas

Plugging Commenced 8-30-90 1 PM

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-30-90 1:45

The plugging proposal was approved on 8-29-90 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? YES

Producing Formation U. Winfield Depth to Top 2820 Bottom 2831 T.D. 2853

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	315'	0
Dakota	water	900	1100	4 1/2	2929	0
U. Winfield	water	2820	2830			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 2 sx cottonseed hulls - 125 sx 60/40 poz w/ 8% gel, filled csg - pres to 1000# - pump 15 sx 60/40 poz dn annulus of 4 1/2 csg - pres to 1000# - held.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address 24 S/ Lincoln, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bartling Oil Co. SEP 12 1990

STATE OF Kansas COUNTY OF Seward, ss. 9-12-90

Terry W. Maxwell

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W Maxwell


(Address) P. O. Box 800, Liberal, KS

67905

SUBSCRIBED AND SWORN TO before me this 11 day of September, 19 90

Londa D Maxwell
Notary Public

My Commission Expires: 12-13-92



JOB LOG

15071-20485-0000

WELL NO. 2 LEASE Foster

TICKET NO. 818010

CUSTOMER Barrling

PAGE NO.

JOB TYPE Cement 4 1/2 Prod.

DATE 12-16-89

FORM 2013 R-2

CHART NO.	TIME	RATE (RPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
								24, 20, 40
								GREEN HAY KS.
	11:00							Request on loc.
	11:30							On loc.
								Rag lay down collar
	14:00							Howco - Hook up - C. calculate
	14:15							Howco Hook up - Cement
		f				250		Howco - Start Cement
		f	242			270		Howco - Finish Cement
		f				200		Howco - Wash Pumps & Lines
		f	46					Howco - Start Disp.
		f						Howco Finish Disp. 46 BBL
		41				400		Howco - Pump Floor
						1500		Howco - Floor Hold
	13:00							Howco - Cement <u>46 BBL</u>

DATE LOGGED THIS JOB

AUG 27 1990

W. H. HARRIS