


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rush County. Sec. 29 Twp. 16 Rge. 16 (E) (W) X
Location as "NE/CNW&SW&" or footage from lines. SE SE SE
Lease Owner Frontier Oil Company
Lease Name Moore Well No. B-1
Office Address 310 South Main Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9-5-70 19
Plugging completed 9-11-70 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	214	None
				4 1/2	3562'	2614'.57

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved into location. Dug cellar. Rigged up unit. Sanded off bottom at 3450' and dumped 4 sacks of cement. Put on control head, had 23" stretch at 1600 psi. Loaded hole. Shot pipe at 2600' and laid down 35 joints of casing. Laid down a total of 79 joints of 4 1/2" casing. Pumped cellar out, took off control head and put on plug container. Plugged well with 3 sacks of hulls, 20 sacks of gel and 100 sacks of 6% pozmix.

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas 67530
(Address)



Subscribed and Sworn to before me this 15 day of September, 1970
My commission expires May 27, 1973

Notary Public.

15-165-26343-0000

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1970
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

No. 1 Moore "B"

CASING RECORD:	COMPANY: Frontier Oil Company	DESCRIPTION:
8 5/8" @ 214' w/150 sx cement	CONTRACTOR: Red Tiger Drilling Company	SE SE SE 29-16S-16W Rush County, Kansas
4 1/2" @ 3562' w/150 sx cement	COMMENCED: August 15, 1970	
	COMPLETED: August 26, 1970	
TOTAL DEPTH: 3575'		ELEVATION: 1995' RB 1992' DF


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	15	
Rock & Shale	15	215	
Shale & Shells	215	360	
Shale & Sand	360	528	
Sand	528	736	
Shale	736	900	
Shale & Lime	900	1085	
Anhydrite	1085	1125	
Shale & Shells	1125	1320	
Shale & Lime	1320	3010	
Lime	3010	3575	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 2 day of September, 1970.



Virginia K. Albert
Notary Public

My Commission Expires:

July 23, 1974