

K-165-01895-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE 1/4 NE 6 E

SEC. 16 TWP. 16 RGE. 16

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Ray Braek.

Operator Coel Lebach Address Box #308 - Hays - Kans.

Field _____ County Rush

Total Depth 2540 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 1040 ft. Circulated with cement.
5 1/2 Casing Set at 3534 ft. Cemented with 75 sacks cement.
Plugged back to 3525 ft. with chat. Dumped
5 sacks of cement at 3525 ft. Shot off & pulled
the 5 1/2 casing - Mud to 275 ft. Set Rock Bridge
& 15 sacks of cement at 275 ft. Mud to 30 ft.
Plug & 10 sacks of cement at the surface.

PLUGGING
FILE SEC. 15 TWP. 16 R. 16
BOOK PAGE 49 LINE 1

C. W. Stoenish
District Conservation Agent

Date 12-13-50