

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT



API Number 15-165-20, 820-0000

245 North Water
Wichita, KS 67202

Operator's Full Name CHIEF DRILLING COMPANY, INC. \$60.52

Complete Address 905 CENTRY PLAZA, WICHITA, KANS. 67202

Lease Name CHAPLINGER Well No. #1

Location C-5 1/2 - NE - NW Sec. 20 Twp. 16 Rge. 16 (East) (West)

County PUSH. Total Depth 1862 FT

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated BOTTOM JOINT OF S.P. PARTED - ABANDONED

Plugging Contractor B. T. B. DRILLING (JOHN HARMBRUSTER RIG 2)

Address 515 UNION STR. WICHITA, KS License No. _____

Operation Completed: Hour 10:00 PM Day 14 Month DEC Year 1980

The above well was plugged as follows:

8 5/8" 945 FT S.P. CUM W/400 ST COMMON-2% GEL-3% CMC. + COMMON-2% GEL-2% CMC.

ORDERED 115 ST 50/50 PORMIX 4% GEL. + 8 5/8" PLUG. (ELV. 1969 FT.)

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1 ST PLUG @ 840 FT W/ 40 ST CNT.

2 ND PLUG @ 360 FT W/ 30 ST CNT.

3 RD PLUG - SOLID BRIDGE - HULLS - PLUG. @ 40 FT W/ 10 ST CNT.

5 ST IN RHT HOLE.

CEMENTED BY ALLIED OCT. 17 1980

BOTTOM JOINT OF S.P. FELL OFF.

CONSERVATION DIVISION
Wichita, Kansas

ABANDONED HOLE. PLAN TO SHUT RIG + DRILL ANOTHER HOLE

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 1-22-81

NO. 3998-W