

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company
Complete Address P. O. Box 1201, Wichita, Kansas
Lease Name Suppes Well No. 1- V
Location SW NE NE Sec. 11 Twp. 16 Rge. (E) (W) 16
County Rush Total Depth 3524'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Red Tiger Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 2:45 P Day 26 Month 3 Year 1974

The above well was plugged as follows:

RTD 3524' 10 3/4 csg set at 202' cwc 225 sk. Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 185' set cementing plug and displaced 30 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 15 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/28/74
INV. NO. 8813-W

Signed: Res. F. Massey
Well Plugging Supervisor