

KANSAS

R STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Hinkle Oil Company

Complete Address: 1016 Un.Center Wichita, Kansas

Lease Name Urban Well No. 1

Location NE SW NW Sec. 10 Twp. 16 Rge. 16 (E) (W) X

County Rush Total Depth 3540'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Knights Casing Plg.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 8:30 P Day 11 Month 7 Year 1967

The Above well was plugged as follows:

Total Depth 3540' 8 5/8 csg set at 912' cwc.

4 1/2 csg set at 3520' cw 150 sc cement.

Filled with sand to 3500' and dumped 4 sc cement with dump bailer.

Recov. 2416' of 4 1/2 csg.

Squeezed thru 8 5/8 plg container with 25 sc gel and 100 sc 50-50 poz cement with

6 % gel. Shutin pres 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUL 17 1967

Signed: Rio 7 Massey
Well Plugging Supervisor

DATE 7/17/67
INV. NO. 5946-4
CONSERVATION DIVISION
Wichita, Kansas