

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-101-20,691-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Donald C. Slawson Oil Producer

Complete Address 200 Douglas Bldg., Broadway @ Douglas, Wichita, KS 67202

Lease Name YORK L.L. Well No. 1

Location E 1/2 SESE Sec. 11 Twp. 16 Rge. 30 (East)(West)

County LANE Total Depth 4490'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Co.

Address _____ License No. _____

Operation Completed: Hour: 3:30 AM Day: 9 Month: 8 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The 8 5/8" o.p. set @ 370' w/ 235 Sx. Cmt.

1ST plug @ 1200' w/ 70 Sx. Cmt.

2ND plug @ 360' w/ 40 Sx. Cmt.

3RD S.B. rubber plug - 8 5/8" @ 40'

4TH 40'-0' w/ 10 Sx

5TH IN THE RATHOLE w/ 10 Sx. Cmt.

Cement used - 50-50 Poz-mix w/ 4% gel - 3% C.C.

Cementing by Haliburton Services.

Amount of Surface Casing: 370'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: R. Bartlett
Conservation Division Agent
order by S. Dumont

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED
DATE 8-19-82
952-W

RECEIVED
AUG 16 1982
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
15-101-20691-0000