

15-165-36137-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 10 1966

Operator's Full Name Hummon Oil, Inc.,

Complete Address: 821 Union National Building Wichita, Kansas

Lease Name Maier Well No. 1

Location C S/2 NE SE Sec. 24 Twp. 16 Rge. 16 (E) (W) X

County Rush Total Depth 3576

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Burt Drilling Co.

Address: Great Bend, Kansas License No. _____

Operation Completed: Hour 5:30 P Day 6 Month 10 Year 1966

The Above well was plugged as follows:

RTD 3576' 8 5/8 csg set at 325' cwc 225 sc.

Gunned pits, circulated heavy mud, set cementing plug at 450' and displaced 30 sc cement thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/3 sc hulls and 8 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: John Massey
Well Plugging Supervisor

DATE 10/10/66

INV. NO. 4096-4