

15-165-20343-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Frontier Oil Company

Complete Address 1720 Wichita Plaza Wichita, Kansas

Lease Name Moore "B" Well No. 1

Location SE SE SE Sec. 29 Twp. 16 Rge. (E) (W) 16

County Rush Total Depth 3575'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbesasing Pulling

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 12 N Day 11 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3575' 8 5/8 csg set at 214' cwc

4 1/2 csg set at 3562' cw 150 sk cmt.

4 1/2 csg PBTD 3524' with top perf. (3465-3470)

Filled 4 1/2 csg W/sd (3450-3524) Dumped 4 sk cmt W/dump bailer. (3415-3450)

Cutoff and recovered 2600' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/3 sk hulls, plug and 100 sk

50-50 poz 6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Macey

Well Plugging Supervisor

DATE 9-14-70INV. NO. 2527-W