

15-165-01838-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Frontier Oil Co
Complete Address: 580 4th Natl Bk Bldg Wichita, Kansas
Lease Name Honderick Well No. 1
Location CNW Sec. 31 Twp. 16 Rge. (E) (W) 16
County Rush Total Depth 3617
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Barnes & Sons
Address: Russell, Kansas License No. 9
Operation Completed: Hour 10:30AM Day 29 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 210' circulated with cement - 4 1/2" 3180' top cement 2675' - ~~per~~
PB to 3145' - perf 3032'
Filled with sand to 3000', set 3 sax cement with dump bailer - pulled
2645' 4 1/2" - pumped hole full heavy gel mud (35 sax Gel), pumped cementing
plug followed by 125 sax cement.
Mudding and cementing by Sun Cementing Co - 500# pump pressure - 300#
standing pressure on completion.

I hereby certify that the above well was plugged as herein stated.

DATE 4/2/63
INV. NO. 6820-41

Signed: *Edon Petty*
Well Plugging Supervisor