

K. 135-1958-0000

Form CP-3
Rev. 6-26-62

VP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mull Drg Co
Complete Address: 1625 Wichita Plaza Wichita, Kans
Lease Name Mc Nair Well No. 1
Location CNE NE Sec. 32 Twp. 20 Rge. (E) (W) 24
County Ness Total Depth 4450
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: Forbes Casing Plugging
Address: Great Bend, Kans License No. 49
Operation Completed: Hour 3:30PM Day 2 Month 2 Year 64

The Above well was plugged as follows:

8 5/8" 250' circulated with cement - 4 1/2" 4449' with 125 sax cement - perf 4381'

Sand back to 4370', set 3 sax cement with dump bailer - pulled 3700'
4 1/2" to 500', circulated hole with heavy mud through 4 1/2" (21 sax gel)
displaced 20 sax cement through 4 1/2" at 500', heavy mud to 230', displaced 20
sax cement through 4 1/2" at 230', heavy mud to 55', set bridge and 10 sax cement
to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: *[Signature]*
Well Plugging Supervisor

INVOICED

DATE 2/11/64
INV. NO. 8008-14