

15.135.20992-0000



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 18 1975  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Texaco, Inc.

Complete Address Box 2420, Tulsa, Oklahoma 74102

Lease Name Minnie Pember Well No. 1

Location C NE SE Sec. 20 Twp. 20 Rge. (E) (W) 24

County Ness Total Depth 4500'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by Halliburton Cementing Co.

Address        License No.       

Operation Completed: Hour 12 N Day 14 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 4500' 8 5/8 csg 327' cwc 250 sk.

5 1/2 csg 4500' cw 250 sx cem.

5 1/2 csg DV tool set 2200' cwc. No pipe recovered.

5 1/2 csg PBD 4392' & perf. (4326-4330)

Mixed & pumped down 5 1/2 csg with 25 sk 50-50 poz cem 6% -35 sk gel & water W/300 lbs

hulls -released plug & 75 sx 50-50 poz cem 6%. PP 1100 lbs. SIP 700 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 3/20/75

INV. NO. 1022-W