

15.135.20542-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Strata Drilling, Inc.

Complete Address Box 355 Great Bend, Kansas

Lease Name Copeland Well No. 1

Location C SW NW Sec. 17 Twp. 20 Rge. (E) (W) 24

County Ness Total Depth 4442'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 5:10 P Day 28 Month 12 Year 1971

The above well was plugged as follows:

RTD 4442' 8 5/8 csg set at 296' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt
cmt thru drill pipe. Heavy mud to 290' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Messing
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4957-U