

15-135-20077-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name R. V. Lehner

Complete Address: P. O. Box 398 Ness City, Kansas

Lease Name Cranston Well No. 2

Location C SE NE Sec. 25 Twp. 20 Rge. 24 (E) (W) X

County Ness Total Depth 4413

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Strata Drlg. Inc.,

Address: Wichita, Kansas License No.

Operation Completed: Hour 8 A Day 8 Month 11 Year 1967

The Above well was plugged as follows:

RTD 4413' 8 5/8 csg set at 289' cwc 165 sc.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 300' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: R. F. Massey
Well Plugging Supervisor

INVOICED

DATE

INV. NO.